

EchoWater Facility FOG Station System Repairs, RFB# 8514  
Bidding Period Questions thru **10/08/25**

Question No.	Question	Response
1	Material cert required (Buy America(n), AIS, BABA)?	Since this project is not funded by Federal or State grants, the requirement does not apply to this project.
2	When is the anticipated NTP for the project?	Refer to Addendum#3 Item 3.01
3	No Electrical specification and drawings have been provided. Please confirm there is NO electrical scope required for this bid.	Yes, there is no electrical scope required for this bid. The District staff will perform electrical scope. For more information, refer to Section 01 14 00-3 1.02 Work Items.
4	Confirm no electrical disconnect and reconnection of new equipment (Rock traps and grinders) is included in this bid package.	SacSewer staff will disconnect electrical and refer to 1.02 WORK ITEMS, Table 2. Contractor Requirements, Requirement Number A under Section 01 14 00-3 for more information.
5	What does the removal and reattachment of the FOG piping Heat Tracing system referenced in note 6 on G02 entail?	FOG piping has a heat tracing system. Contractor shall protect the wiring while performing work and re-attach/re-install on new piping using cloth electrical tapes such as 3M 69.
6	Aside from the 2" EPDM elastomeric tube insulation on the piping up to the rocks, is all blanket and other forms of insulation to be salvaged and reinstalled on new piping systems?	Yes, re-use insulation blankets and install at piping connection joints per General Note 7 on Drawing Sheet G09.
7	Is the mount/stand for the new rock trap to be provided BY THE OWNER?	No, the mount/stand is part of the unit.
8	How far is the gantry system to be placed/stored from where it is being removed?	Leave it at FOG station.
9	How do the grinder control panels mount to the ground? Will grout pads be required?	Yes, grinder control panel is mounted to the ground similar to pipe support using four 1/2" SS anchors and grout pad.
10	Can we work on both lines simultaneously?	Yes, the contractor may work on both FOG lines simultaneously since the FOG station is currently not operatable.

EchoWater Facility FOG Station System Repairs, RFB# 8514  
Bidding Period Questions thru **10/08/25**

Question No.	Question	Response
11	Can a working foreman also be the designated Safety Manager?	Yes.
12	Is all work to be performed on standard day shifts Monday through Friday?	Yes.
13	Confirm what work will be required to occur during a shutdown.	The FOG station is not currently in operation.
14		
15		