



**ADDENDUM NO. 2**

RFB#8517 LDLD Road Rehabilitation Project

Receipt of this addendum must be acknowledged in the space provided in the cost response form.



DATE: 10/23/2025

BY Scott A. Mueller

SCOTT MUELLER  
PROJECT ENGINEER

This Addendum No. 2 shall be incorporated into and made part of the above referenced contract documents for RFB#8517. See next page.



Addendum Item	Section and Page or Drawing No.	Location and Description of Change
2.01	Volume 1 of 2 Specification 01 57 23/3.01	<p>ADD the following paragraph to the section:</p> <p>C. Fiber rolls and/or straw wattles are not required to be installed along the length of the LDLD Roadway sections. The Contractor shall expect, at a minimum, to provide BMP protection at the LDLD Exposed Liner Runoff Zone Basin Outlet Structures(Drain Inlets) located in LDLDs 1 thru 5. The expectation will be straw wattles with gravel filled bag anchors, or hay bales surrounding the drain inlet structure, approximately 25 L.F. in length for each location. <b>NO STEEL BAR OR WOODEN LATH ANCHORS ARE ALLOWED ON THE EXISING LINER MATERIAL!!!</b> This general requirement does not relieve the Contractor from implementing Best Management Practices to prevent the direct and indirect contribution of any excessive sediment or contaminant into the roadway ditches and basins.</p>
2.02	N/A	Attached please find the responses to Contractor Questions received to date.

## Questions and Answers - Addendum 2

### RFB#8517 LDLD Road Rehabilitation Project

1. What is the oil type required to perform application of asphaltic emulsion?

*Emulsified Asphalt shall be SS-1h or CSS-1h per Caltrans Section 94.*

2. For BMP measures is silt fencing less desired than straw rolls?

*See Addendum item 2.01.*

3. Please verify that there are no QSP/QSD/NOI needed by the contractor?

*There is no requirement for QSP/QSD/NOI on the project. However, per Specification Section 01 57 23/1.03/A./2.: "The Contractor shall designate a Storm Water Pollution Prevention Coordinator. This person shall have previous experience in erosion and sediment control..."*

4. Please verify that there is no general permit required of air resource board requirements?

*No, a general permit is not required for this project, however, the Contractor shall adhere to the requirements for California Air Resources Board (CARB) on page 26 of the Request for Bid document.*

5. Please provide locations of construction water access to the contract. Is there a cost associated with construction water? If so, what is that cost?

*Construction Water Location (Water Well) is shown on GI001. The well has a "J Stand" fill type and water is free to the contractor for use on the project.*

6. Is there a designated dumpsite location onsite for the spoils coming off of this project? If so please provide a location?

*The Contractor shall be responsible for hauling excess spoils/debris offsite in accordance with laws and regulations regarding disposal of such materials.*

7. What BMPS for SWPPP will be required if any? i.e. DI protection in ponds or any waddle outside of the road footprint? Please provide count and/or LF of required.

*See Addendum item 2.01.*